



**CALCOLO SCAVI E RIPORTI**

SCAVI:  
 TRONCO 1= (A1.1+A1.3)XTR1=(1+126)X39,9=5067MC  
 TRONCO 2= (A2.1+A2.3)XTR1=(1+154)X42,3=6556MC  
 TRONCO 3= (A3.1+A3.3)XTR1=(1+118)X34,5=4105MC

TOTALE SCAVI= 5067+6556+4105=15728MC

RIPORTI:  
 TRONCO 1= A1.2XTR1=1,5X39,9=60MC  
 TRONCO 2= A2.2XTR1=1X42,3=42MC  
 TRONCO 3= A3.2XTR1=1X34,5=34MC

TOTALE RIPORTI=60+42+34 = 136 MC

**TOTALE SCAVI E RIPORTI = 15728+136= 15864MC**  
**AREA TOTALE DI SCAVO = 5370 MQ**

